



Specification for proposed storage building on northern elevation of the Appley Public Conveniences

The storage facility is approx. 4m x 4m and will be constructed as follows:

Contract 1:

Groundworks

Base up to damp course

Base up to DPC will be constructed as itemised below and as shown on accompanying plan:

Footings

Footings to be dug level to average 1 metre below ground level 600mm wide.

Concrete to be poured level to 300mm deep

Blockwork

Blockwork to be 100mm concrete blocks constructed with cement (3 parts sand to 1 part cement).

Floor

Floor to be made up as follows:

- 150mm crushed and consolidated hardcore.
- 50mm sand blinding.
- 1200 gauge polythene DPM
- 100mm normal performance concrete to a level float finish to match level of existing toilet floors.